



ARMY PUBLIC SCHOOL B D BARI

(10+2) Affiliated to CBSE under Affiliation No - 780016 , School Code - 23521

PO - Industrial Estate, Tehsil - Bari Brahmana, District - Samba, J&K(UT) - 181133

Website - www.apsbdbari.org, Email - apsbdbari@gmail.com, apsbdbari@awesindia.edu.in, Contact No - 9419248070

TECHNICAL EVALUATION FOR CONSTRUCTION OF SYNTHETIC VOLLEYBALL COURT AT ARMY PUBLIC SCHOOL BD BARI, DISTRICT SAMBA, JAMMU & KASHMIR (UT)

S.No	Particulars	Complied/ Not Complied	Remarks
1.	Playing area of Synthetic Volleyball Court – 18 mtrs x 9 mtrs		
2.	Total area required (free zone) 28 mtrs x 15 mtrs		
3.	Soil Treatment		
	(a) Excavation of ground upto depth of 9 inches from the ground		
	(b) Removing all weeds and grass from its roots of the ground area		
	(c) Removing of excavated soil		
4.	Civil Work		
	(a) Excavation upto 9 inches, watering, compaction and dressing, excavated giving a gradient of 1:120 towards one side depending where the main drainage is located (Excavation levels determines so as to keep the finished levels minimum 6 inches above the surrounding areas)		
	(b) Application of weed killer and soil stabilizer		
	(c) Providing and laying 6 inches thick WBM, in one layer of 4.5" with hand broken at site, the same will be compacted, watered all the voids will be filled with kapchies and quarry soils and mohurum		
5.	Asphalting		
	(a) Providing and applying tack coat at 0.5kg per Sq mtr after thorough cleaning of surface and prior to laying of asphalt macadam, compacted thickness with bitumen.		
	(b) Laying of 40mm thick asphalt macadam with bitumen 80/100 grade with PPT with graded sieved aggregate funder to 25mm in bitumen.		
	(c) Laying of 25mm thick asphalt concrete manually/paver with bitumen grade 80/100 – 4% to 5% with graded aggregate with maximum size of ½" graded down to fines of 25% and allowed to cure for 24/30 days maximum the asphalt mix will be with PPT 1.2%		
	(d) Spreading manually grit powder mixed with PPT and cement on the finished asphalt surface to close the porosity of free asphalt and allowing the surface to surface to be dried for minimum 30 days prior to laying of the synthetic surfacing		
6.	All Season Synthetic Surfacing (8 Layer) (18 mtrs x 9 mtrs)		
	(a) Consists of 8 layer Acylic cushion system, one coat of bio cum primer/resurface, two coat layer of heavy cushion, three layers of fine cushion (Rubberized) two layers of colour (Red & Blue) line marking of court (White/Yellow colour)		
7.	Support Wall		
	(a) Dimension of wall (Height 1 ft x Width 9 inches)		
	(b) Brick work cement 1:4 (1 cement : 4 core sand)		
	(c) Providing and laying plaster 12mm cement mortar 1:4 (1 cement : 4 core sand)		





ARMY PUBLIC SCHOOL B D BARI

(10+2) Affiliated to CBSE under Affiliation No - 780016 , School Code - 23521

PO - Industrial Estate, Tehsil - Bari Brahmana, District - Samba, J&K(UT) - 181133

Website - www.apsbdbari.org, Email - apsbdbari@gmail.com, apsbdbari@awesindia.edu.in, Contact No - 9419248070

-2-

TECHNICAL EVALUATION FOR CONSTRUCTION OF SYNTHETIC VOLLEYBALL COURT AT ARMY PUBLIC SCHOOL BD BARI, DISTRICT SAMBA, JAMMU & KASHMIR (UT)

S.No	Particulars	Complied/ Not Complied	Remarks
8.	<u>Volleyball Pole</u>		
	(a) Net & Poles : Net Poles of International Standard. The height of the net measures 2.43 mtr (7 feet from the court ground and the centre) and the poles is of 3" pipes.		
	(b) Volleyball antenna made of fiber with red and white making and synthetic tape for tightening in net and Velcro		
9.	Minimum 12 months of unconditional warranty towards colour fading or any manufacturing defects to the material and installation etc.		
10.	<u>Earnest Money Deposit (EMD) (Enclosed with this evaluation)</u>		
	(a) EMD of Rs 30,000/- (Rupees Thirty Thousand only) to be submitted in the form of Demand Draft/Pay Order/Fixed Deposit Receipt by Schedule banks in favour of Army Public School BD Bari, Bari Brahmana - 184120		
	(b) EMD in the form of cheque will not be accepted.		
	(c) Quotation/Tender received without requisite EMD shall be summarily rejected.		
11.	<u>Performance Guarantee</u>		
	(a) 3% of tender value to be submitted within 15 days upon issue of Letter of Acceptance and before placing work order.		
12.	<u>Security Deposit</u>		
	(a) 5% of the tendered value will be deducted from the bill and will be kept as Security Deposit for 12 months.		
	(b) On completion of 12 months the security deposit amount will be released after carrying out the inspection of the work done by the Board of Officers/Technical team.		

13. No advance payment shall be made. The contractors are requested to send their tenders/quotations duly addressed in sealed envelopes. Tenders/Quotations will be dropped into the box kept in APS BD Bari upto 20 Jan 2023 (1500hrs). No tender/quotation will be accepted beyond the stipulated time frame. Tender/Quotation should reach to the under mentioned address:-

The Principal
Army Public School BD Bari
PO Industrial Estate BD Bari
Tehsil Bari Brahmana, District Samba J&K
PIN - 181133



Tender/Quotation envelopes should be duly marked "TECHNICAL EVALUATION FOR
CONSTRUCTION OF SYNTHETIC VOLLEYBALL COURT"



ARMY PUBLIC SCHOOL B D BARI

(10+2) Affiliated to CBSE under Affiliation No - 780016 , School Code - 23521

PO - Industrial Estate, Tehsil - Bari Brahmana, District - Samba, J&K(UT) - 181133

Website - www.apsbdbari.org, Email - apsbdbari@gmail.com, apsbdbari@awesindia.edu.in, Contact No - 9419248070

-3-

TECHNICAL EVALUATION FOR CONSTRUCTION OF SYNTHETIC VOLLEYBALL COURT AT ARMY PUBLIC SCHOOL BD BARI, DISTRICT SAMBA, JAMMU & KASHMIR (UT)

14. This School reserves the right to change or vary any part thereof at any stage and also reserves the right to withdraw the project, should it become necessary at any stage/reject the tenders/quotations.


15. The tender/quotation of Non GST firm will be rejected.

Note - Please enclose last three years GST returns filled by your firm.

Contractor Name _____
Firm Name _____
Address _____
License No if any _____
Mobile No _____
Signature _____

File No: 833/6/ASBDB/Quo/46

Dated: 12 Jan 2023



(Mrs Neeta Rawal)
Principal