

Website : www.apsbdbari.org
E Mail : apsbdbari@gmail.com
Mb No : 9419248070
Tele : 3381 (Army)

Army Public School BD Bari
PO Industrial Estate BD Bari
Tehsil Bari Brahmana,
District – Samba-181133 (J & K)

833/6/APS BDB/Quo/46

02 Dec 2024

CALL FOR QUOTATION : DEVELOPMENT OF FOOTBALL GROUND

Dear Sir/Madam,

1. It is intimated that market survey board for development of Football ground for students of Army Public School BD Bari is being carried out.
2. You are requested to quote your rates for development of Football ground as per specification/ description mentioned in the Appendix attached to this letter please.
3. The following specifications are also required to be mentioned in the quotation: -
 - (a) Total cost incl GST, freight & any other charges.
 - (b) Discount, if any.
 - (c) Warranty period.
 - (d) Construction period (If required).
4. No advance payment shall be made. The vendors are requested to send their quotations duly addressed in sealed envelopes/through email. Quotations will be dropped into the box kept in APS BD Bari till 08 Dec 2024 (1400hrs). No quotation will be accepted beyond the stipulated time frame. Quotation should reach to the under mentioned address:-

The Principal
Army Public School BD Bari, PO Industrial Estate BD Bari,
Tehsil Bari Brahmana, District Samba-181133 (J&K)

Quotation envelopes should be duly marked "QUOTATIONS FOR _____".

5. The quotation of Non GST firm will be rejected.


Lt Col/Maj
Presiding Officer

Enclosures : as above.

15-12-2024
Lt Col/Maj Presiding Officer

**SPECIFICATION FOR DEVELOPMENT OF FOOTBALL GROUND AT ARMY
PUBLIC SCHOOL - BD BARI**

Sr. No.	Description	Specification/ Scope of work	Area/Qty
1	Dimension	<ul style="list-style-type: none"> ● Total Covered Area - 17,280 Sqm (approx) (180 mt.X 96 mt.) ● Foot Ball Ground - 13100 Sqm (approx) 	
2.	Removal of Existing Fencing	Dismantling G.I chain Link fencing work including angles frame, all gusset plates, bolts, nuts, cutting rivets, welding etc.including dismembering and stacking within 50 meters lead.	1200 Sqm
3.	Leveling of Playground	<p>Earth work in surface excavation not exceeding 30 cm in depth including uprooting of rank vegetation, grass, brush wood, and saplings of girth up to 30 cm above ground level and removal of Malba/rubbish up to a distance of 50 m outside the periphery of the area cleared.</p> <p>Surface leveling of the playground by adding soil or by excavated soil via mechanically (JCB, TRACTOR ROOTER PANJA) than leveling with computerize machines or by manual labour. Complete inequalities not exceeding 15 cm deep and watering and preparation of the surface and smooth surface as directed by APS.</p> <p>Preparation and consolidation of ground with power road roller of 6 to 8 tonnes capacity after adding soil, dressing to camber and consolidating with road roller including making good the undulations etc.</p>	13100 Sqm
4.	Supply & filling of good Earth	Supplying and filling of local good earth (including royalty) by mechanical transport up to a lead of 15km also including ramming and watering of the earth in layers not exceeding 20 cm in including watering, ramming, consolidating and dressing complete.	1000 cum
5	Kerb Stone	Providing and fixing both side running track or near ground level precast cement concrete in kerbs, edgings etc. as per approved pattern and setting in position with cement mortar 1:3 (1 Cement : 3 coarse sand), including the cost of required centering, shuttering complete. 1:1½:3 (1 Cement: 1½ coarse sand(zone-III) : 3 graded stone aggregate 20 mm nominal size) (Thickness 100 mm , above ground 150mm and below ground 200 mm).	1200 mtr.
6.	Football Pole	Fixed type Football pole - Heavy duty 80 mm with & netwise tightening mechanism as per standard	2 Nos.

**SPECIFICATION FOR DEVELOPMENT OF FOOTBALL GROUND AT ARMY
PUBLIC SCHOOL - BD BARI**

