

Website : www.apsbdbari.org
E Mail : apsbdbari@awesindia.edu.in
Contact No: 9419248070 (Civil) & 3381 (Army)

Army Public School BD Bari
PO Industrial Estate BD Bari
Tehsil Bari Brahmana,
District – Samba-181133 (J & K)

833/6/APS BDB/Quo/46 dated 22 Dec 2025

**CALL FOR QUOTATION : CONSTRUCTION OF FRONT BOUNDARY
WALL OF ARMY PUBLIC SCHOOL BD BARI**

Dear Sir/Madam,

1. It is intimated that market survey board for construction of front boundary wall of Army Public School BD Bari is being carried out.
2. You are requested to quote your rates for construction of front boundary wall of Army Public School BD Bari as per specification/description mentioned in the Appendix attached to this letter please.
3. The following specifications are also required to be mentioned in the quotation: -
 - 3.1. Total cost incl GST, freight & any other charges.
 - 3.2. Discount, if any.
 - 3.3. Warranty period.
 - 3.4. Construction period (If required).
4. The vendors are requested to send their quotations duly addressed in sealed envelopes/through email. Quotations will be dropped into the box kept in APS BD Bari till 26 Dec 2025 (1400hrs). No quotation will be accepted beyond the stipulated time frame. Quotation should reach to the under mentioned address:-

The Principal
Army Public School BD Bari, PO Industrial Estate BD Bari,
Tehsil Bari Brahmana, District Samba-181133 (J&K)

Quotation envelopes should be duly marked "QUOTATIONS FOR _____".

5. The quotation of Non GST firm will be rejected.



Lt Col/Maj
Presiding Officer
5271 ASC Bn

Enclosures : as above.

**SPECIFICATION FOR CONSTRUCTION OF FRONT BOUNDARY
WALL OF ARMY PUBLIC SCHOOL BD BARI**

S No	Description	Specification /Scope of work	Area/ Qty	Amount
1.	Construction of front boundary wall of Army Public School BD Bari	Boundary wall measuring 90 metres in overall length, constructed in 230 mm thick brick masonry, with a finished height of approximately 2100 mm above ground level. The wall incorporates a 50 mm thick damp-proof course over a 300 mm wide plinth beam, seated on a stepped concrete foundation having a total depth of 800 mm below natural ground level. The footing steps are considered sequentially reducing from 1000 mm, 900 mm, 750 mm, 600 mm to 450 mm, with corresponding rises of 100 mm, 150 mm, 150 mm and 150 mm, respectively. The design includes 32 brick masonry pillars, each built in 450 mm × 450 mm section, spaced along the wall to receive the fabricated steel grills. The boundary wall further incorporates 31 mild steel grills, each measuring 2550 mm in length and 900 mm in height, with a minimum individual weight of not less than 60 kg. All brick masonry, foundation work, grill fabrication, plastering, finishing, painting, reinforcement, shuttering and associated construction described is calculated based on following parameters:-	Complete work as per specification	
2.		Earth work: Excavation in foundation trenches, pits or drains in all kinds of soil including dressing of sides, ramming of bottoms, disposing of surplus earth within a lead of 50m, and lift up to 1.5m, complete as per drawings and specifications.		
3.		Mud Mat: Providing and laying Plain Cement Concrete (PCC) 1:4:8 (1 cement:4coarses and : 8graded stone aggregate 40 mm nominal size) as leveling course under foundations including curing, compacting and finishing, complete.		
4.		Plain Cement Concrete: Providing and laying PCC of mix 1:2:4 (1cement: 2 coarse sand : 4 graded stone aggregate 20mm nominal size) in foundation and flooring including form work, compacting, curing, and finishing, complete.		
5.		Reinforced Cement Concrete: Providing and laying RCC of mix 1:1.5:3 (1 cement:1.5 coarses and: 3graded stone aggregate 20 mm nominal size) in foundation beams, columns, slabs etc. including formwork, vibration, curing, but excluding cost of reinforcement steel, complete.		
6.		Damp Proof Course: Providing and laying 50mm thick DPC with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 stone aggregate 12.5mm nominal size), including application of a coat of bitumen 85/25 @ 1.7 kg/sqm, complete.		
7		Bitumen Coat: Providing and applying hot applied bitumen primer/coat on Damp Proof Course and wall surfaces as per IS: 3384, applied @ 1.7 kg/sqm, complete.		

S No	Description	Specification /Scope of work	Area/ Qty	Amount
8		Brick Work: Brick work with common burnt clay F.P.S bricks of class designation 7.5, in super structure above plinth level, laid in cement mortar 1:6 (1 cement : 6 coarse sand) including curing and scaf folding, complete.	Complete work as per specification	
9		Cement Plaster: 12mm thick plaster on brick or concrete surfaces with cement mortar1:6 (1cement:6fine sand), finished even and smooth, including curing and scaffolding, complete.		
10.		White Cement Based Putty: Providing and applying 2mm thick white cement based wall putty of approved brand (Birla/JK or equivalent) over plastered surfaces to prepare even and smooth surface, complete.		
11.		Exterior Primer & Paint: Providing and applying exterior cement based primer of approved brand on wall surfaces and finishing with two coats of exterior weather proof paint (Asian/Berger or equivalent), all as per manufacturer's specifications.		
12.		MS Grill: Fabrication, supplying and fixing of mild steel grills, made of flats, angles, square/roundbars, duly welded, fixed in position including one coat of primer and two coats of synthetic enamel paint, complete.		
13.		Steel Reinforcement: Providing, cutting, bending, binding and placing in position thermo-mechanically treated (TMT) steel reinforcement bars conforming to IS 1786, including binding with 16 gauge annealed wire, complete.		
14.		Filling with Available Earth: Filling available excavated earth (excluding rock) in plinth, trenches or foundation in layers not exceeding 20cm, consolidating each deposited layer by ramming and watering, complete.		
15.		Shuttering: Providing and fixing formwork for foundations, footings, columns, beams and other structural members with steel/plywood shuttering plates, propping, centering, including removal of form work after specified period, complete.		
16.		Including complete material, water, disposal of building rubbish material. labour charges & tax		
		Total amount including all type of taxes.		